Sl No	App Qty	Description of work	Approved Rates of K.GOPIREDDY		
			Unit	Rate in Words	Rate in Figures
1	2	3	4	5	6
55	2	Core cutting for taking pipes and bore packing water tight with cement concrete and waterproof ---- All terms and conditions as per the Tender document and as per the direction Engineer-in-Charge	Job	9000.0	Rupees Nine Thousand Only
56	12	Earthwork excavation for foundation of buildings, culverts, water supply, sanitary lines and electrical conduits either in pits or in trenches 1.5m.and above in width, in ordinary soil not exceeding 1.5m.in depth including dressing the bottom and sides of pits and trenches, stacking the excavated soil clear from edges of excavation with lead upto 50 m. after breaking of clods complete as per specifications.specification No.KBS 2.1(a)/2.3.5 ---- All terms and conditions as per the Tender document and as per the direction Engineer-in-Charge	Cum	200.0	Rupees Two Hundred Only
57	10	Providing and laying in position to required level or slope 150mm internal diameter salt glazed stoneware pipes grade A and jointing with stiff mixture of cement mortar in proportion of 1:1, testing of pipes and joints, including cost of materials, labour charges complete as per specifications. Specification No. KBS 12.2.5/12.7 ---- All terms and conditions as per the Tender document and as per the direction Engineer-in-Charge	Rmt	350.0	Rupees Three Hundred Fifty Only
58	12	Refilling available earth around the pipeline, cables in layers not exceeding 20 cms in depth, compacting each deposited layer by ramming after watering with lead upto 50 m and lift upto 1.5m including cost of all labour complete as per specifications. ---- All terms and conditions as per the Tender document and as per the direction Engineer-in-Charge	cum	80.0	Rupees Eighty Only
59	4	Providing stoneware gully trap of approved quality and make fixing inm-15 and plastering with CM 1:3 wherever necessary. (Rate includes cost of all materials, fixtures and lead). (15cms x10cms) ---- All terms and conditions as per the Tender document and as per the direction Engineer-in-Charge	No.	275.0	Rupees Two Hundred Seventy Five Only
60	12	Earthwork excavation for foundation of buildings, culverts, water supply, sanitary lines and electrical conduits either in pits or in trenches 1.5m.and above in width, in ordinary soil not exceeding 1.5m.in depth including dressing the bottom and sides of pits and trenches, stacking the excavated soil clear from edges of excavation with lead upto 50 m. after breaking of clods complete as per specifications.specification No.KBS 2.1(a)/2.3.5 ---- All terms and conditions as per the Tender document and as per the direction Engineer-in-Charge	cum	200.0	Rupees Two Hundred Only
61	1.2	Providing and fixing in trenches galvanised medium grade 50mm dia nominal bore with all fittings (earth work in trenches to be measured and paid for seperately) including cost of all materials, labour charges,HOM of equipments and testing complete as per specifications (From Sump to OHT) ---- All terms and conditions as per the Tender document and as per the direction Engineer-in-Charge	Rmt.	540.0	Rupees Five Hundred Forty Only
62	12	Refilling available earth around the pipeline, cables in layers not exceeding 20 cms in depth, compacting each deposited layer by ramming after watering with lead upto 50 m and lift upto 1.5m including cost of all labour complete as per specifications.) ---- All terms and conditions as per the Tender document and as per the direction Engineer-in-Charge	cum	80.0	Rupees Eighty Only
63	4	Providing and fixing 50mm dia nominal bore gun metal non-return valve horizontal type of approved make including cost of all materials,labour charges,HOM of equipments and testing complete as per specifications ---- All terms and conditions as per the Tender document and as per the direction Engineer-in-Charge	No.	1500.0	Rupees One Thousand Five Hundred Only
64	4	Providing and placing on terrace , polyethylene water storage tanks (1000 ltr capacity) ---- All terms and conditions as per the Tender document and as per the direction Engineer-in-Charge	No.	9000.0	Rupees Nine Thousand Only
65	25.6	Earthwork excavation for foundation of structures as per drawings and technical specification, including setting out, construction of shoring and bracing, removal of stumps and other deleterious matter, dressing of sides and bottom, backfilling the excavation earth to the extent required and utilising /tramsporting the remaining earth locally upto1.0kms lead - Ordinary Rock (not required blasting)- Manual means) ---- All terms and conditions as per the Tender document	Cum	70.0	Rupees Seventy Only
66	0.8	Providing and laying in position plain cement concrete of mix 1:3:6 with OPC Cement @220kgs with 40mm and down size graded granite metal coarse aggregate @0.892 cum and fine aggregates @0.465 cum machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation including cost of all materials, labour, 110M of machinery, curing complete as per specifications . Specification No. KBS4.1,4.2 ---- All terms and conditions as per the Tender document and as per the direction Engineer-in-Charge	Cum	5400.0	Rupees Five Thousand Four Hundred Only

Gopireddy

Contractor

Executive Engineer,
Project Division, Yelahanka Zone

Executive Engineer
Project Division
Yelahanka Zone
Bangalore

Sl No	App Qty	Description of work	Approved Rates of K.GOPIREDDY		
			Unit	Rate in Words	Rate in Figures
1	2	3	4	5	6
67	2.02	Providing and laying in position reinforced cement concrete of design I mix M25 with OPC cement @340 Kg with 20mm and downsize graded granite metal coars aggregates @0.70 cum and fine aggregates @0.47 cum with superplasticisers @ 3 liters confirming to IS9103-1999 Reaffirmed -2008 at machine mixed concrete laid in layers not exceeding 15 cms thick, vibrated for all works in foundation for footings, pedestals, retaining wall returns walls, walls(any thickness) including attached pilasters, coloumns, pillars, posts, struts, buttresses bed blocks, anchor blocks & plinth etc., including cost of all materials labour HOM of machinary curing complete as per specifications, specifications No KBS-4.1, 4.6 specification No:KBS4.1,4.6(PWD SR 2016-17)(Page No.13 item No.4.10) ---- All terms and conditions as per the Tender document and as per the direction Engineer-in-Charge	Cum	6500.0	Rupees Six Thousand Five Hundred Only
68	2.02	Extra for use of water proofing compound in Cement concrete of mix 1:1:2, at one kg of compound per bag of cement. ---- All terms and conditions as per the Tender document and as per the direction Engineer-in-Charge	Cum	260.0	Rupees Two Hundred Sixty Only
69	7.68	Providing and removing centering, shuttering, strutting, propping etc., and removal of from work for sides and soffits of beams, beam haunchings, cantilever griders, bressumers and lintels not exceeding 1 m in depth including cost of all materials, labour complete as per specifications. Specification No. KBS 4.6.2 ---- All terms and conditions as per the Tender document and as per the direction Engineer-in-Charge	Sqm	260.0	Rupees Two Hundred Sixty Only
70	5.12	Providing and removing centering, shuttering, strutting, propping etc., and removal of from work for flat surface such as suspended floors, roofs landings, balconies and likes, thickness upto 200mm including cost of all materials, labour complete as per specificationSpecification No. KBS 4.6.2 - 0-5.0mts Ht ---- All terms and conditions as per the Tender document and as per the direction Engineer-in-Charge	Sqm	565.0	Rupees Five Hundred Sixty Five Only
71	43.2	Providing and constructing load bearing wall with solid concrete blocks having block density not less than 1800kg/cum having a minimum average compressive strength of 4.00N/mm2 confirming to IS 2185(Part 1):2005 and constructed with CM 1:4, as per IS 2572:2005 including cost of all materials labour charges, scaffolding , curing , hire charges of machineries etc., complete as per specfications . KBS No.5.4 with solid concrete blocks of size 40x20x20cm ---- All terms and conditions as per the Tender document and as per the direction Engineer-in-Charge	Sqm	1000.0	Rupees One Thousand Only
72	0.24	Providing TMT Steel reinforcement for RCC work including straightening, cutting, bending, hooking placing in position lapping and/ or welding wherever required typing with binding wire and anchoring to the adjoining members wherever necessary complete as per design(laps, hooks and wastage shall not be measured and paid) cost of materials labour, HOM of machinery complete as per specifications, Specification No KBS 4.6.3 -do- TMT bars Fe 500(PWD SR 2016-17)(Page No.1 item No.4.46.2) ---- All terms and conditions as per the Tender document and as per the direction Engineer-in-Charge	Tonne	75000.0	Rupees Seventy Five Thousand Only
73	16.96	Filling available excavated earth (excluding rock) in sides of foundations upto plinth in layers not exceeding 20 cms. in depth, compacting each deposited layer by ramming after watering with lead upto 50 m. and lift upto 1.5 m. including cost of all labour complete as per specifications. specification. No. KBS 2.9. ---- All terms and conditions as per the Tender document and as per the direction Engineer-in-Charge	Cum	100.0	Rupees One Hundred Only
74	42.24	Providing 20 mm thick cement plaster in single coat with CM 1:3 to stone masonry / concrete surface including rounding off corners wherever required smooth rendering: Providing and removing scaffolding, including cost of materials, labour, curing complete as per specification. ---- All terms and conditions as per the Tender document and as per the direction Engineer-in-Charge	Sqm	250.0	Rupees Two Hundred Fifty Only
75	4.4	Providing 12mm thick cement plastering in single coat with cement mortar 1:3 to ceiling I including rounding off corners wherever required smooth rendering, Providing and removing scaffolding, including cost of materials, labour, curing complete as per specification. ---- All terms and conditions as per the Tender document and as per the direction Engineer-in-Charge	Sqm	185.0	Rupees One Hundred Eighty Five Only
76	0.72	Providing and fixing MS door for sump including cost of labour, materials and one coat of primer paint and two coats of enamel painting etc, as directed by the engineer in charge of work. ---- All terms and conditions as per the Tender document and as per the direction Engineer-in-Charge	Sqm	3700.0	Rupees Three Thousand Seven Hundred Only

Contractor

Executive Engineer
Project Division, Yelahanka Zone

Executive Engineer
Project Division
Yelahanka Zone
Bangalore

Sl No	App Qty	Description of work	Approved Rates of K.GOPIREDDY		
			Unit	Rate in Words	Rate in Figures
1	2	3	4	5	6
77	300	Open Conduit System Supplying heavy gauge PVC conduit pipe .....dia ..... mm thick confirming to IS 2509 with suitable size bends, junction boxes, adhesive paste etc., and fixing using inverted wood plugs in case of RCC ceiling and RCC wall / stone structure or rawl plugs in case of brick walls and cement plastering the damaged portion using heavy gauge saddles at an interval of 700mm using NF screws. 19/20mm dia 2mm thick ---- All terms and conditions as per the Tender document and as per the direction Engineer-in-Charge	Mtr	50.0	Rupees Fifty Only
78	260	b) 25mm dia 2mm thick ---- All terms and conditions as per the Tender document and as per the direction Engineer-in-Charge	Mtr	60.0	Rupees Sixty Only
79	40	Concealed Conduit System: Supplying heavy guage PVC conduit pipe ...mm dia ...mm thick confirmingto IS 2509 with suitable size bends, Metal/PVCjunction boxes, adhesive paste etc, and running before concreting the slab. The conduit should be tied to the reinforcement rods by using binding wires and unused ways of junction boxes and pipe ends should be covered using PVC end enclosures run with 18SWG GI fish wire where ever necessary. 19/20mm dia 2mm thick ---- All terms and conditions as per the Tender document and as per the direction Engineer-in-Charge	Mtr	40.0	Rupees Forty Only
80	30	b) 25mm dia 2mm thick ---- All terms and conditions as per the Tender document and as per the direction Engineer-in-Charge	Mtr	50.0	Rupees Fifty Only
81	120	Groove Cutting : Supplying heavy guage PVC conduit pipe ...mm dia ...mm thick with suitable size bends, Metal/PVCjunction boxes, adhesive paste etc, by groove cutting in wall and fixing by using U or J hooks and cement plastering up to the wall surface and run with 18SWG GI fish wire through out the conduit where ever necessary. 19/20mm dia 2mm thick ---- All terms and conditions as per the Tender document and as per the direction Engineer-in-Charge	Mtr	50.0	Rupees Fifty Only
82	80	b) 25mm dia 2mm thick ---- All terms and conditions as per the Tender document and as per the direction Engineer-in-Charge	Mtr	55.0	Rupees Fifty Five Only
83	50	Supplying and flush mounting powder coated / galvanized metal box suitable for mounting modular switch plates. The box should be firmly flush mounted after due groove cutting in Brick/Stone/C.C wall 1-3Way ---- All terms and conditions as per the Tender document and as per the direction Engineer-in-Charge	Each	85.0	Rupees Eighty Five Only
84	40	b) 4-5Way ---- All terms and conditions as per the Tender document and as per the direction Engineer-in-Charge	Each	90.0	Rupees Ninety Only
85	10	c) 6Way ---- All terms and conditions as per the Tender document and as per the direction Engineer-in-Charge	Each	100.0	Rupees One Hundred Only
86	30	d) 8Way ---- All terms and conditions as per the Tender document and as per the direction Engineer-in-Charge	Each	125.0	Rupees One Hundred Twenty Five Only
87	20	e) 10-12Way ---- All terms and conditions as per the Tender document and as per the direction Engineer-in-Charge	Each	150.0	Rupees One Hundred Fifty Only
88	50	Supplying and fixing superior quality modular switch mounting polycarbonate plate with necessary supporting back plate with required nos. of machine screws, bolts nuts etc., complete on the existing metal/PVC box. 1-3Way ---- All terms and conditions as per the Tender document and as per the direction Engineer-in-Charge	Each	85.0	Rupees Eighty Five Only
89	40	b) 4-5Way ---- All terms and conditions as per the Tender document and as per the direction Engineer-in-Charge	Each	110.0	Rupees One Hundred Ten Only
90	10	c) 6Way ---- All terms and conditions as per the Tender document and as per the direction Engineer-in-Charge	Each	165.0	Rupees One Hundred Sixty Five Only
91	30	d) 8Way ---- All terms and conditions as per the Tender document and as per the direction Engineer-in-Charge	Each	175.0	Rupees One Hundred Seventy Five Only
92	20	e) 10-12Way ---- All terms and conditions as per the Tender document and as per the direction Engineer-in-Charge	Each	260.0	Rupees Two Hundred Sixty Only
93	104	Supplying and fixing of modular switch/ Socket/stepped electronic fan regulator/ dimmer/telephone socket etc on existing modular switch plate as per IS 3854 and IS 1293. 6Amps one way ---- All terms and conditions as per the Tender document and as per the direction Engineer-in-Charge	Each	55.0	Rupees Fifty Five Only
94	8	b) 6Amps 3way socket ---- All terms and conditions as per the Tender document and as per the direction Engineer-in-Charge	Each	85.0	Rupees Eighty Five Only
95	32	c) Stepped Fan Regulator ---- All terms and conditions as per the Tender document and as per the direction Engineer-in-Charge	Each	275.0	Rupees Two Hundred Seventy Five Only
96	12	d) 16Amps one way switch ---- All terms and conditions as per the Tender document and as per the direction Engineer-in-Charge	Each	100.0	Rupees One Hundred Only
97	12	e) 6/16Amps universal socket ---- All terms and conditions as per the Tender document and as per the direction Engineer-in-Charge	Each	125.0	Rupees One Hundred Twenty Five Only
98	2	f) TV/Telephone socket ---- All terms and conditions as per the Tender document and as per the direction Engineer-in-Charge	Each	75.0	Rupees Seventy Five Only

Contractor

Executive Engineer
Project Division, Yelahanka Zone

Executive Engineer
Project Division
Yelahanka Zone
Bangalore

Sl No	App Qty	Description of work	Approved Rates of K.GOPIREDDY		
			Unit	Rate in Words	Rate in Figures
1	2	3	4	5	6
99	24	supplying and wiring adopting loop system in existing PVC conduit / casing capping using 1100 v grade , copper conductor flexible multistrand FRLS PVC insulated, 2 x1.5sq.mm cable confirming to the GTP, without switch, the other end of the wires shall be terminated with sufficient loose length in a wood /PVC cound block. complete for each outlet. Short point up to 3Mtr from tapping point to out let via switch box ---- All terms and conditions as per the Tender document and as per the direction Engineer-in-Charge	Each	125.0	Rupees One Hundred Twenty Five Only
100	90	b) Medium point above 3Mtr up to 6Mtr from tapping point to out let via switch box ---- All terms and conditions as per the Tender document and as per the direction Engineer-in-Charge	Each	200.0	Rupees Two Hundred Only
101	30	c) Long point above 6Mtr up to 10Mtr from tapping point to out let via switch box ---- All terms and conditions as per the Tender document and as per the direction Engineer-in-Charge	Each	325.0	Rupees Three Hundred Twenty Five Only
102	10	d) Two Outlet in a row, above 3.0M unto 6.0M from tapping point to outlet via switch box. ---- All terms and conditions as per the Tender document and as per the direction Engineer-in-Charge	Each	400.0	Rupees Four Hundred Only
103	4	e) Three Outlet in a row, above 6.0M unto 10.0M from tapping point to outlet via switch box. ---- All terms and conditions as per the Tender document and as per the direction Engineer-in-Charge	Each	565.0	Rupees Five Hundred Sixty Five Only
104	46	Supplying and fixing metal Fan box with Round Hook. ---- All terms and conditions as per the Tender document and as per the direction Engineer-in-Charge	Each	85.0	Rupees Eighty Five Only
105	500	Wiring for lighting/power circuit using one of FRLS PVC insulated 1100v grade, multistrand Copper with low conductor resistance single core cable in open or concealed system of wiring with specified IS-694:1990 & comfirming to GTP of Group-A . 1.5 sqmm ---- All terms and conditions as per the Tender document and as per the direction Engineer-in-Charge	Mtr	15.0	Rupees Fifteen Only
106	1000	b) 2.5 sqmm ---- All terms and conditions as per the Tender document and as per the direction Engineer-in-Charge	Mtr	25.0	Rupees Twenty Five Only
107	300	c) 25mm dia 2mm thick ---- All terms and conditions as per the Tender document and as per the direction Engineer-in-Charge	Mtr	40.0	Rupees Forty Only
108	100	d) 6 sqmm ---- All terms and conditions as per the Tender document and as per the direction Engineer-in-Charge	Mtr	60.0	Rupees Sixty Only
109	40	b) 2.5 sqmm ---- All terms and conditions as per the Tender document and as per the direction Engineer-in-Charge	Mtr	95.0	Rupees Ninety Five Only
110	2	Supplying and fixing regular MCB distribution boards on wall/wood board/flush mountin using required clamps, bolts, nuts with provision for fixing suitable type capacity MCB's single phase/3 phase/single door with powder coated painting. Made out of 14 SWG M.S enclosure. Double door 4 way TP & N ---- All terms and conditions as per the Tender document and as per the direction Engineer-in-Charge	Mtr	2300.0	Rupees Two Thousand Three Hundred Only
111	2	b) 6 way TP & N ---- All terms and conditions as per the Tender document and as per the direction Engineer-in-Charge	Mtr	2800.0	Rupees Two Thousand Eight Hundred Only
112	2	b) 12 way SP & N ---- All terms and conditions as per the Tender document and as per the direction Engineer-in-Charge	Mtr	1600.0	Rupees One Thousand Six Hundred Only
113	20	Supplying and fixing miniature circuit breakers on existing MCB distribution boards using necessary fixing materials and 'C' Type curve, indicator ON/OFF, energy cross-3 with Short circuit breaking capacity of 10K and complete wiring as required confirming to IEC 60898 5-32Amps SP ---- All terms and conditions as per the Tender document and as per the direction Engineer-in-Charge	Each	400.0	Rupees Four Hundred Only
114	4	b) 5-32Amps TPN ---- All terms and conditions as per the Tender document and as per the direction Engineer-in-Charge	Each	1540.0	Rupees One Thousand Five Hundred Forty Only
115	4	c) 40-63Amps TPN ---- All terms and conditions as per the Tender document and as per the direction Engineer-in-Charge	Each	1900.0	Rupees One Thousand Nine Hundred Only
116	2	Supplying, fixing and wiring eaarth Earth Leakage Miniature Circuit Breaker [ELMCB] 240/250V upto 300mA sensitivity on existing wood/panel board. 16-25Amps 2Pole ---- All terms and conditions as per the Tender document and as per the direction Engineer-in-Charge	Each	2400.0	Rupees Two Thousand Four Hundred Only
117	2	b) 32-40Amps 4Pole ---- All terms and conditions as per the Tender document and as per the direction Engineer-in-Charge	Each	3250.0	Rupees Three Thousand Two Hundred Fifty Only
118	17000	Fabricating supplying and mounting MS box made out ...SWG suitable for floor I wall mounting, fully weather proof with provision for better heat dissipation, provided with hinged front cover, equipped with tamper proof locking arrangements, with suitable size clamps with necessary cable entry pipe with gland and box should be finished with 2 coats of red oxide primer paint and finally finished with approved colour enameled metal paint etc., complete ---- All terms and conditions as per the Tender document and as per the direction Engineer-in-Charge	Sqcm	0.3	Rupees And Paise Thirty Only

Contractor

Executive Engineer
Project Division, Yelahanka Zone

Executive Engineer
Project Division
Yelahanka Zone
Bangalore

	Description of work	Unit	Rate in Words	Rate in Figures
2	3	4	5	6
2	Supplying .....amps rated 3phase with neutral bus bar using required capacity electrolytic aluminum strips covered with heat shrinkable coloured PVC sleeve, mounted on phenoliciFRP/DMC insulator which are mounted on powder coated 40x6mm M.S.flat frame work in existing panel board. The bus bar shall have suitable holes for termination of incoming and outgoing cables as per IS specification with necessary bolts, nuts and washers etc., complete. ---- All terms and conditions as per the Tender document and as per the direction Engineer-in-Charge	mtr	2000.0	Rupees Two Thousand Only
120 6	Supplying fixing angle iron frame work fabricated out of M.S angle iron .. And m.S flat.... With bolts, washers etc., and painted with two coats of red oxide and then two coats of approved paint. 40x40x6 mm ---- All terms and conditions as per the Tender document and as per the direction Engineer-in-Charge	mtr	250.0	Rupees Two Hundred Fifty Only
121 6	a) 50x100x50x6 mm ---- All terms and conditions as per the Tender document and as per the direction Engineer-in-Charge	mtr	620.0	Rupees Six Hundred Twenty Only
122 2	Supplying and fixing Moulded Case Circuit Breaker (MCCB) .over the existing wood/panel board using necessary screws, bolts, nuts and wiring complete. Protection of Overload and Short circuit with thermal Magnetic/Micro processor release and Earth Fault as per IS-13947. (Ieu= Ics) ---- All terms and conditions as per the Tender document and as per the direction Engineer-in-Charge	Each	5700.0	Rupees Five Thousand Seven Hundred Only
123 2	Supplying of multi function degital meter with three line backlight LCD type display for voltage , current frequency, power, power factor, KVA, KWH,KVAR suitable for 3 phase, 4 wire LT network with IP 54degree of protection and completely wired as required with communication port and class 0.5s accuracy. ---- All terms and conditions as per the Tender document and as per the direction Engineer-in-Charge	Each	7500.0	Rupees Seven Thousand Five Hundred Only
124 2	Supplying, fixing and wiring 0 to 600Volts 96x96mm AC Voltmeter on existing panel/wood board. ---- All terms and conditions as per the Tender document and as per the direction Engineer-in-Charge	Each	350.0	Rupees Three Hundred Fifty Only
125 2	Supplying, fixing and wiring 50/5 to 400/5Amps 5VA burden Current Transformer. Class 0.5 accuracy with Tape Wound ---- All terms and conditions as per the Tender document and as per the direction Engineer-in-Charge	Each	450.0	Rupees Four Hundred Fifty Only
126 6	Supplying and fixing of LED type panel board indicating lamp with required colour suitable for 220v A.C. 50 Hz 12/24v D.C ---- All terms and conditions as per the Tender document and as per the direction Engineer-in-Charge	Each	400.0	Rupees Four Hundred Only
127 2	Supplying of on load change over switches 4 poles, AC-23A Duty, 415V, 50Hz, AC Supply. ---- All terms and conditions as per the Tender document and as per the direction Engineer-in-Charge	Each	6250.0	Rupees Six Thousand Two Hundred Fifty Only
128 40	Supplying of 1.1 KV LT UG cable having aluminum conductor PVC insulated, extruded inner sheathed, galvanized, steel strip (except 2CX10Sq.mm wire armoured) confirming to IS-3975:1990 (No.of Strip indicated in GTP & extruded PVC outer sheathed armoured cable with specified IS-1554 Part-1:1988 & confirming to GTP of GROUP-A 3.5 core 50 sqmm ---- All terms and conditions as per the Tender document and as per the direction Engineer-in-Charge	Mtr	250.0	Rupees Two Hundred Fifty Only
129 60	b) 4 core 16 sqmm ---- All terms and conditions as per the Tender document and as per the direction Engineer-in-Charge	Mtr	135.0	Rupees One Hundred Thirty Five Only
130 60	Labour charges for laying of 1.1 KV class UG cable in existing trench GI pipe / stoneware pipe / on wall / on pole as required. 25 sqmm to 75 sqmm ---- All terms and conditions as per the Tender document and as per the direction Engineer-in-Charge	Mtr	15.0	Rupees Fifteen Only
131 100	b) 6 sqmm 16 Sqmm ---- All terms and conditions as per the Tender document and as per the direction Engineer-in-Charge	Mtr	8.0	Rupees Eight Only
132 96	Digging of trench of 0.6m deep x 0.50 mtr wide refiling the trench to the required ground level and consolidating etc., complete.(As per Civil SR KSRB I-2, P-7)In soil (ordinary) ---- All terms and conditions as per the Tender document and as per the direction Engineer-in-Charge	Mtr	70.0	Rupees Seventy Only
133 96	providing and filling sand in exvated trench to cover already laid UG cable to a depth of 150mm alround the cable. ---- All terms and conditions as per the Tender document and as per the direction Engineer-in-Charge	Mtr	90.0	Rupees Ninety Only
134 56	providing and laying in position 100mm dia stone ware pipe in existing trench ---- All terms and conditions as per the Tender document and as per the direction Engineer-in-Charge	Mtr	200.0	Rupees Two Hundred Only
135 20	Supplying and fixing of class A (medium duty) GI pipe of wall thick ness not less than 3.25mm on pole/wall/drain crossing with necessary clamping arrangements for UG cable of 1.1 KV class. 65 mm ---- All terms and conditions as per the Tender document and as per the direction Engineer-in-Charge	Rmt	550.0	Rupees Five Hundred Fifty Only

Contractor

Executive Engineer
Project Division, Yelahanka Zone

Project Division
Yelahanka Zone
Bangalore

Sl No	App Qty	Description of work	Approved Rates of K.GOPIREDDY		
			Unit	Rate in Words	Rate in Figures
1	2	3	4	5	6
136	2	Supplying and fixing L.T cast iron pot heads suitable for 1.1 Kv class UG cable filled with necessory bitumin / insulating compound Complete with terminals, clamps, bolts, nuts and washers. ---- All terms and conditions as per the Tender document and as per the direction Engineer-in-Charge	Rmt	600.0	Rupees Six Hundred Only
137	4	Supplying and fiixing of heavy duty cable glands suitable for UG cable of 1.1 KV class (metal only) ---- All terms and conditions as per the Tender document and as per the direction Engineer-in-Charge	Each	375.0	Rupees Three Hundred Seventy Five Only
138	24	Supplying tinned copper lugs and crimping and wiring to terminal point for wire of the following sizes. 50 sqmm Long Barrel ---- All terms and conditions as per the Tender document and as per the direction Engineer-in-Charge	Each	60.0	Rupees Sixty Only
139	24	b) 6 sqmm ---- All terms and conditions as per the Tender document and as per the direction Engineer-in-Charge	Each	5.0	Rupees Five Only
140	8	Supplying fixing and wiring earth electrode for grounding of lifts, transformers, DG sets etc using 40mm dia 2.9mm thick 2.5 mtr long GI pipe with GI funnel with mesh and suitable size reducer fixed on the top of the earth electrode. The funnel should be enclosed in a CC chamber of 400x400x400mm with a cast iron cover. The earth electrode shall have staggered holes of 12mm dia and the electrode should be covered 150mm alround with alternate layers of salt and charcoal from the bottom of the CC chamber. The connection from the electrode is to be established through GI strip using GI bolts and nuts. ---- All terms and conditions as per the Tender document and as per the direction Engineer-in-Charge	Each	4317.0	Rupees Four Thousand Three Hundred Seventeen Only
141	120	Supplying and running of GI/Copper strips for grounding connections, using necessary fixing materials as required. GI strip 25x6mm ---- All terms and conditions as per the Tender document and as per the direction Engineer-in-Charge	Mtr	100.0	Rupees One Hundred Only
142	32	Supplying of 2' feet - LED PVC Square Batten ..W with high quality diffuser with Life of 25000 burning hours & 70% lumen maintenance with CRI > 80. Power Input: 220-240V @ 50Hz & Power factor >0.9 along with CE approved drivers. 5 years Warranty against any manufacturing defect working under standard electrical condition LED light fighting 4' - 28 watts ---- All terms and conditions as per the Tender document and as per the direction Engineer-in-Charge	Each	1600.0	Rupees One Thousand Six Hundred Only
143	34	Supplying and fixing PBBC/Bakelite straight or slant batten holder and wiring with 60w/230 volts lamp. ---- All terms and conditions as per the Tender document and as per the direction Engineer-in-Charge	Each	150.0	Rupees One Hundred Fifty Only
144	40	Supplying capacitor type ceiling fan complete with down rod blades, shackle, canopies etc., for operation on 230 volts, 50 cycles. Single phase AC supply conforming to ISS-374-1979 and with double ball bearing system. 56" Sweep (1400mm) Regular moduel ---- All terms and conditions as per the Tender document and as per the direction Engineer-in-Charge	Each	2200.0	Rupees Two Thousand Two Hundred Only
145	4	Supplying exhaust fan of 1440 RPM of 300mm (12") sizewith bracket blades complete for light duty suitable to operate on 230V 50Hz. AC Supply ---- All terms and conditions as per the Tender document and as per the direction Engineer-in-Charge	Each	1600.0	Rupees One Thousand Six Hundred Only
146	72	Fixing all types and all capacities fluorescent / false ceiling/spotlight/ CFLfittings indoor on the wall/ ceiling/rafters / girders using 23/0.0076" twin twisted RVC insulated wires, required nos of round blocks and clamps (if required) ---- All terms and conditions as per the Tender document and as per the direction Engineer-in-Charge	Each	95.0	Rupees Ninety Five Only
147	56	Fixing fluorescent light using 2mtr long 19mm 18 SWG enameled braised conduit of two Nos. rod pendent with ball socket with check nuts all nickel plated) ---- All terms and conditions as per the Tender document and as per the direction Engineer-in-Charge	Each	500.0	Rupees Five Hundred Only
148	40	Fixing a ceiling /Wall mounting fan of all capacities and all types to the existing 'S' hook with fan regulator to the existing board together with supplying and fixing 5 amps.ceiling rose,necessary length of 23/0.0076 inch PVC insulated twin twisted copper wire of approved quality, mounted on a suitable aize wooden board and wired ---- All terms and conditions as per the Tender document and as per the direction Engineer-in-Charge	Each	200.0	Rupees Two Hundred Only
149	40	Fixing a ceiling fan with extra length of GI pipe of class B 19mm dia for down rod ---- All terms and conditions as per the Tender document and as per the direction Engineer-in-Charge	Each	150.0	Rupees One Hundred Fifty Only
150	40	Fixing one Exhast fan in the nitch already left in the wall with bolts and nets and 5 amps. Ceiling rose with sufficient length of 23 / 0.0076 inch PVC insulated twin core wire. ---- All terms and conditions as per the Tender document and as per the direction Engineer-in-Charge	Each	400.0	Rupees Four Hundred Only

Contractor

Executive Engineer
Project Division, Yelahanka Zone

Project Division
Yelahanka Zone
Bangalore